

SOLAR WAREHOUSE MIAMI-DADE TEST REPORT

SCOPE OF WORK

ASTM D1761 FASTENER WITHDRAWAL AND LATERAL RESISTANCE EVALUATION OF MR-SW-HP-8S - SWH PV MOUNTING SYSTEM, 8" VERSION STANDOFF

REPORT NUMBER

R5185.02-106-18 R0

TEST DATES 09/17/24 - 09/23/24

ISSUE DATE 10/21/24

RECORD RETENTION END DATE 09/23/34

MIAMI-DADE COUNTY NOTIFICATION NO. ATI 24056


LABORATORY CERTIFICATION NO. 22-0428.14

PAGES

12

DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2828 (07/12/22) © 2017 INTERTEK



MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

REPORT ISSUED TO

SOLAR WAREHOUSE 9628 Valley Blvd Rosemead, California 91770

SECTION 1

SCOPE

Products: MR-SW-HP-8S - SWH PV Mounting System, 8" Version Standoff

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by Solar Warehouse to evaluate MR-SW-HP-8S - SWH PV Mounting System, 8" Version Standoff in accordance with ASTM D1761 for fastener withdrawal and lateral resistance. Results obtained are tested values and were secured by using the designated test method. Testing was conducted at the Intertek B&C test facility in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

| For INTERTEK B&C: | | | |
|-------------------|----------------------|--------------|----------------------|
| COMPLETED BY: | Cag S. Saylor | REVIEWED BY: | Tanya Dolby, P.E. |
| TITLE: | Technician III | TITLE: | Manager, |
| | Materials Laboratory | | Engineering Services |
| SIGNATURE: | | SIGNATURE: | |
| | | | |
| | | | |
| DATE: | 10/21/24 | DATE: | |
| CSS:dmc/td/kae | | | |

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 2

TEST METHOD

The specimens were evaluated in accordance with the following:

ASTM D1761-20, Standard Test Methods for Mechanical Fasteners in Wood and Wood-Based Materials, Sections 4-13 Fastener Withdrawal and Sections 14-21 Lateral Fastener Resistance

SECTION 3

MATERIAL SOURCE

The materials were provided by Solar Warehouse. The following was received in good condition on 7/31/24:

- (24) Sets of MR-SW-HP-8S SWH PV 8" Mounting Systems
- (4) Tubes of Chem Link M-1 Universal Adhesive & Sealant

Refer to the product description photos in Section 9. The materials were tested as received, except for preparing test specimens from the original materials. Representative materials/test specimens will be retained by Intertek B&C for a minimum of ten years from the test completion date.

SECTION 4

TEST EQUIPMENT

| NAME | ICN/DESCRIPTION |
|-----------------|-----------------|
| INSTRON UTM | ICN: INT02020 |
| 30 kN Load Cell | ICN: INT02023 |
| Moisture Meter | ICN: Y003141 |

Note: Calibration certificates are available upon request.

SECTION 5

LIST OF OFFICIAL OBSERVERS

| NAME | COMPANY |
|-------------------|--------------|
| Cag Saylor | Intertek B&C |
| Dawn M. Chaney | Intertek B&C |
| Tanya Dolby, P.E. | Intertek B&C |

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 6

TEST PROCEDURES

All conditioning of test specimens and test conditions were at standard laboratory conditions, unless otherwise reported. Refer to the test related photos in Section 9.

ASTM D1761 - Fastener Withdrawal, Sections 4-13

Withdrawal evaluations were performed on 19/32" plywood sheathing. Each piece of sheathing was predrilled with a 3/16" lead hole through the sheathing and rafter. The 5/16" hanger bolt fastener was then installed and sealed using Chem Link M-1 Universal Sealant. After the sealant cured, specimens were loaded onto an Instron UTM (ICN: INT02020) equipped with a 30 kN load cell (ICN: INT02023). Load was applied at a rate of 0.10 in/min until failure was achieved. The specimens were determined to have failed when the load dropped 25% from the peak value. The moisture content of the sheathing pieces was recorded using a Delmhorst Moisture Meter (ICN: Y003141).

ASTM D1761 - Lateral Fastener Resistance, Sections 14-21

Lateral resistance evaluations were performed on 19/32" plywood sheathing. Each piece of sheathing was predrilled with a 3/16" lead hole through the sheathing and rafter. The 5/16" hanger bolt fastener was then installed and sealed using Chem Link M-1 Universal Sealant. After the sealant cured, load was applied at a rate of 0.10 in/min using an Instron UTM (ICN: INT02020) equipped with a 30 kN load cell (ICN: INT02023). The specimens were tested beyond the maximum load representing a complete lateral failure. The moisture content of the sheathing pieces was recorded using a Delmhorst Moisture Meter (ICN: Y003141).

SECTION 7

TEST SPECIMEN DESCRIPTIONS

| TEST PROCEDURE | NUMBER OF SPECIMENS | NOMINAL SPECIMEN DIMENSIONS |
|---|---------------------|--------------------------------|
| ASTM D1761, Sections 4-13 Fastener Withdrawal | 10 | 16" x 17.5" |
| ASTM D1761, Sections 14-21 Fastener Lateral Resistance | 10 | 16" x 17.5" |

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 8

TEST RESULTS

ASTM D1761, Sections 4-13 - Fastener Withdrawal

| SPECIMEN ID | | MAXIMUM FORCE | DISPLACEMENT (in) | FAILURE MODE |
|----------------|-------------------|------------------|----------------------|----------------------|
| 1 | (%) 8.0 | (lbf) 2,940 | 1.145 | fastener withdrawal |
| 1 | 0.0 | 2,940 | 1.145 | Tasteller withurawat |
| 2 | 8.1 | 3,080 | 1.114 | clip fracture |
| 3 | 7.9 | 2,510 | 0.508 | fastener withdrawal |
| 4 | 7.6 | 3,330 | 1.151 | fastener withdrawal |
| 5 | 7.7 | 2,540 | 1.021 | fastener withdrawal |
| 6 | 7.8 | 3,130 | 0.930 | fastener withdrawal |
| 7 | 8.4 | 2,710 | 0.642 | fastener withdrawal |
| 8 | 8.1 | 1,950 | 0.454 | fastener withdrawal |
| 9 | 7.8 | 1,930 | 0.550 | fastener withdrawal |
| 10 | 7.6 | 2,910 | 0.954 | fastener withdrawal |
| Average | 7.9 | 2,703 | 0.847 | |
| Std. Dev. | 0.25 | 477 | 0.28 |] |

ASTM D1761, Sections 14-21 - Lateral Fastener Resistance

| SPECIMEN ID | MOISTURE CONTENT (%) | MAXIMUM FORCE (lbf) | DISPLACEMENT (in) | FAILURE MODE |
|----------------|----------------------------|---------------------------|----------------------|--------------|
| 1 | 8.0 | 1,280 | 5.271 | Clip Break |
| 2 | 7.8 | 934 | 4.397 | Clip Break |
| 3 | 7.6 | 799 | 4.187 | Clip Break |
| 4 | 7.6 | 802 | 4.372 | Clip Break |
| 5 | 8.0 | 872 | 4.473 | Clip Break |
| 6 | 9.6 | 778 | 4.268 | Clip break |
| 7 | 8.7 | 823 | 4.062 | Clip break |
| 8 | 8.2 | 1030 | 4.542 | Clip Break |
| 9 | 7.7 | 795 | 4.062 | Clip break |
| 10 | 9.2 | 1,150 | 5.167 | Clip break |
| Average | 8.2 | 926 | 4.480 | |
| Std. Dev. | 0.70 | 173 | 0.42 | |

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 9

CONCLUSION

The requested test method does not contain specific performance requirements. Results are reported as obtained.

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 10 PHOTOGRAPHS



Photo No. 1 Material as Received




Photo No. 2 ASTM D1761 Fastener Withdrawal Test Setup

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE



Photo No. 3 ASTM D1761 Fastener Withdrawal at Test End (typical)




Photo No. 4 ASTM D1761 Fastener Withdrawal at Test End (typical)

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE



Photo No. 5 ASTM D1761 Fastener Withdrawal at Test End (typical)



Photo No. 6 ASTM D1761 Lateral Fastener Resistance Test Setup

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE



Photo No. 7 ASTM D1761 Lateral Fastener Resistance Test in Progress



Photo No. 8 ASTM D1761 Lateral Fastener Resistance at Test End (typical)

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE




Photo No. 9 ASTM D1761 Lateral Fastener Resistance at Test End (typical)




Photo No. 10 ASTM D1761 Lateral Fastener Resistance Failure Detail (typical)

MIAMI-DADE TEST REPORT FOR SOLAR WAREHOUSE

Report No.: R5185.02-106-18 R0 Date: 10/21/24

SECTION 11

REVISION LOG

| REVISION # | DATE | PAGES | REVISION |
|------------|----------|-------|-----------------------|
| 0 | 10/21/24 | N/A | Original Report Issue |